

COUNTY OF TUSCOLA
DEPARTMENT OF BUILDINGS AND GROUNDS

125 W. Lincoln St
CARO, MI 48723

MICHAEL MILLER

Director

THOMAS MCLANE

Assistant Director

TO: INTERESTED CONTRACTORS

FROM: MIKE MILLER

DATE: August 10, 2022

RE: New Asphalt Drive and Unloading Area

Tuscola County will be accepting bids on New Asphalt Drive and Unloading area for the County Recycling Center. The following specifications shall be considered in your bid:

Location:

Tuscola County Recycling
987 Ellington ST
Caro, MI 48723

The County is looking to asphalt an existing driveway and unloading area. The project will be about 5500 square feet.

These areas have 8-10 inches of stone crete already installed a year ago.

Project to be completed in 2022.

Contractor Shall:

1. Verify gradients and elevations.
2. Verify that existing base is sufficient.
3. Verify compacted subbase is dry and ready to support paving and imposed loads.
4. Apply primer on aggregate base and subbase at a uniform rate of 1/3 gallon per square yard.
5. Use clean sand to blot excess primer.
6. Apply tack coat on asphalt surfaces over subgrade surface at uniform rate of 1/3 gallon per square yard.
7. Place asphalt binder course within 24 hours of applying primer.
8. Place binder course to compacted thickness.
9. Place wearing course within 24 hours of placing and compacting binder course. When binder course is placed more than 24 hours before placing wearing course, clean surface and apply a tack coat before placing wearing course.
10. Place wearing course to compacted thickness.
11. Compact each course by rolling to specified density. Do not displace or extrude pavement from position. Hand compact in areas inaccessible to rolling equipment.

12. Perform rolling with consecutive passes to achieve even and smooth finish without roller marks.
13. Flatness: Maximum variation of ¼ inch measured with 10-foot straight edge.
14. Schedule Compacted Thickness: Within ¼ inch

Accepted Materials:

1. Aggregate for Binder Course Mix: In accordance with State of Michigan Department of Transportation latest standards. Bituminous mix 13A performance grade 64-22. Thickness 2.0 inch compacted.
2. Aggregate for Wearing Course Mix: In accordance with State of Michigan Department of Transportation latest standards. Bituminous mix 13A performance grade 64-22. Thickness 1.5 inch compacted
3. Primer/Tack Coat: Homogenous, medium curing liquid asphalt, in accordance with Michigan Department of Transportation.

Other:

1. Contractor shall provide Liability and Workmen Comp insurance.
2. Contractor shall provide all necessary tools and equipment.
3. Qualified personnel shall perform all work.

For questions or to view the project please call 989-672-3756. Please do not ask Recycling staff questions on the project.

Sealed proposals labeled "Recycling Drive" shall be submitted to the Tuscola County Controllers office, Atten: Buildings and Grounds 125 W. Lincoln st, Caro, and MI 48723 no later than 4:00 pm on August 19, 2022

Please call if you have questions: 989-672-3756

Disclaimer

Tuscola County reserves the right at its sole discretion to reject any and all proposals received without penalty and not to enter a contract as a result of this RFP. The County also reserves the right to negotiate separately with any source whatsoever in any manner necessary to attend to the best interests of the County, to waive irregularities in any proposal and to accept a proposal which best meets the needs of the County, irrespective of the bid price."

By submitting a bid, the bidder is acknowledging that there will be no contractual relationship between Tuscola County and the bidder until both parties have formally approved and signed a written contract to be developed by Tuscola County legal counsel.

The County reserves the right to make an award without further discussion of any proposal submitted. Therefore, the proposal should be submitted initially on the most favorable terms which the offer can propose. There will be no best and final offer procedure. The County does reserve the right to contact an offer for clarification of its proposal."

